

ASSAM TEA EMPLOYEES PROVIDENT FUND ORGANIZATION
(Formerly known as The Assam Tea Plantations Provident Fund & Pension Fund Scheme & D.L.I Scheme)
"Nidhi Bhawan" Basistha, Lalmati, N.H. - 37, Guwahati – 781029
Phone: 2300108, 2300604, 2300742, 2304263 Fax: 0361-2302602 E-Mail: atppf@live.com website: atppf.nic.in

TENDER NOTICE

No: PF/H.O/CC/D.G.Foundation/2024 _____ DT _____


Sealed tender affixing Court Fee stamp of Rs.8.25 (non refundable) are invited by the undersigned from registered appropriate Contractors in prescribe Form for the following works will be received in the office of the ATEPFO, Nidhi Bhawan , Lalmati, Basistha, N.H.37, Guwahati-29 upto 1.00 PM on 23-12-2024 and opened at 2.00 PM on the same day. If the office happens to be closed on the date of receiving and opening of tenders as specified above the tenders will be received and opened on the next working day at the same time and venue.

1. Name of works : "Providing , fitting and fixing of a Roof Truss Shed and Foundation Bed for New 25KVA D.G set at H.O complex, ATEPFO,Guwahati-29" .
2. Estimated. Value : Rs. 1,13,815.00/-
3. Rate to be quoted : On supplied prescribed Form's bill of quantities and total Quoted value also added. (including all taxes).
4. Time of Completion : 7 (seven) days from the date of issue of formal work order.
5. The upto date I.T, GST, Registration, Trade License Certificate will have to be enclosed with tender The office reserves the right to accept/reject any or all quotation without assigning any reason whatsoever.

Addl.P.F.Commissioner
A.T.E.P.F.O

Memo No :PF/H.O/CC/ D.G.Foundation/2024 169-70 Date 19.12.2024
Copy to: 1. Notice Board
2. System Manager .

Addl.P.F.Commissioner
A.T.E.P.F.O



Tender Form

Name of Work :- Providing, fitting and fixing of a Roof Truss Shed and foundation Bed for A New 25 KVA D.G. Set at H.O. Complex, ATEPFO, Guwahati-29

SL.NO	DESCRIPTIONS OF ITEMS	UNIT	QTY	RATE	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth,1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by engineer-in charge. 2.6.1 all kinds of soil	CUM	5.11	RS.	RS.
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in : 6.1.1 Cement mortar 1:4 (1 cement : 4 coarse sand)	CUM	1.62	RS.	RS.
3	Steel reinforcement for R.C.C.work including staightening, cutting, bending, placing in position and binding all complete upto plinth level. 5.22.6 Thermo-Mechanically Treated bars of grade Fe-500D or more	CUM	175	RS.	RS.
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth level : 4.1.5 1:3:6 (1 Cement : 3 coarse sand (zone- III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	CUM	0.463	RS.	RS.
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 4.1.2 1:½ : 3 (1 Cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	CUM	1.73	RS.	RS.



6	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. 10.16.1 hot finished welded type tubes	Kg	280	RS.	RS.
7	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%) total coated thickness with zinc coating 120 grams per sqm as per is : 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18	sqm	8.6	RS.	RS.
8	12.51 Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50mm (+0.05%) total coated thickness, Zinc coating 120 grams per sqm as per is : 277, in 240	Rm	3.7	RS.	RS.
9	Applying priming coat : 13.50.3 with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	Rm	40	RS	RS.
10	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specification: 13.48.3 painting steel work with deluxe multi surface paint to give an even shade. Two or more coat applied @ 0.90ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	Rm	40	RS	RS
11	15 MM CEMENT PLASTER ON THE ROUGH SIDE OF SINGLE OR HALF BRICK WALL OF MIX : 13.2.1 1:4 (1 CEMENT : 4 FINE SAND)	sqm	5.04	RS.	RS.



12	Providing soling in foundation and under floor with stone/best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete. (a). Brick on flat soling.	sqm	6.2	RS.	RS.
----	---	-----	-----	-----	-----

Total Rs=

Add GST 18% :-

Total (in words) :-

Contractor's Name :-

Address :-

Registration No :-