



ASSAM TEA EMPLOYEES PROVIDENT FUND ORGANIZATION

(Formerly known as The Assam Tea Plantations Provident Fund & Pension Fund Scheme & D.L.I Scheme)

"Nidhi Bhawan" Basistha, Lalmati, N.H. - 37, Guwahati – 781029

Phone: 2300108, 2300604, 2300742, 2304263 Fax: 0361-2302602 E-Mail: atppf@live.com website: atppf.nic.in


TENDER NOTICE

No. PF/CC/REP & PAINT/DIB/ZO/2023 309-10 DT. 3/5/2023

Sealed tender affixing Court Fee Stamp of Rs.8.25 (non.refundable) are invited by the undersigned from registered appropriate Contractors in prescribed Form for the following works will be received in the office of the ATEPFO, Nidhi Bhawan, Lalmati, Basistha, N.H. 37, Guwahati-29 upto 1.00 P.M on 15-05-2023 and opened at 2.00 P.M on the same day. If the office happens to be closed on the date of receiving and opening of tenders as specified above the tenders will be received and opened on the next working day at the same time and venue.


1. Name of works : "Repairing & Painting of Dibrugarh Z/O, ATEPFO, Milan Nagar "Dibrugarh.
2. Estimated.Value : Rs. 3,15,338/.
3. Rate to be quoted : On supplied prescribed Form's bill of quantities and total Quoted value also added.(Including all taxes).
4. Earnest Money : 2% (2% for General & 1% for ST/SC/OBC/MOBC) on total Quoted value infavour of Secretary-um-P.F.Commissioner, ATEPFO, Guwahati-29 inform of Demand Draft/Fixed Deposit.
5. Time of Completion : 30 (thirty) days from the date of issue of formal work order.
6. The upto date I.T.,GST, Registration, Trade Licence Certificates will have to be enclosed With quotations. The office reserves the right to accept/reject any or all quotations without assigning any reason whatsoever.

Yours faithfully


Secretary-Cum-P.F Commissioner
A.T.E.P.F.O

Memo No : PF/CC/REP & PAINT/DIB/ZO/2023 / _____ dt. _____.

Copy to : 1. The Director, Information & Public Relation, Assam, Dispur, Guwahati.
2.System Manager, Computer Cell to upload in the office website.


Secretary-Cum-P.F Commissioner
A.T.E.P.F.O

Clauses:

1. All terms and conditions as per Assam, APWD F-2 (modified) Form
2. Details particulars may be seen in the office of the Secretary-Cum-PF Commissioner, Guwahati-29 in any working days during office hours.
3. Tender papers etc for the work may be obtained from the office of the undersigned during office hours on any working day on or before 12-05-2023 upto 1PM.
4. All materials of good quality shall be arranged by the contractor.
5. Site at ATEPFO office complex Dibrugarh.
6. The upto date income tax clearance certificate and Registration certificate, GST etc will have to be produced at the time of issue of tender papers & enclosed with Tender. Failing which Tender will not be accepted.
7. If the office remain closed due to any reason on 15-05-2023 the tender will be received by the undersigned upto 1 PM on the next working day and will be opened at 2 PM on the same day.
8. The undersigned reserves the right to accept or reject any tender without assigning any reason thereof.
9. No T & P of any kind shall be issued.



TENDER FORM

NAME OF WORK:- "Repairing & Painting of Dibrugarh Z/O, ATEPFO, Milan Nagar".

SL.NO	DESCRIPTION	QNTY	UNIT	RATE	AMOUNT
1	Wall Painting (one coat) with plastic emulsion paint, approved brand and manufacture (Asian paint/Berger paint/ICI paint/ j & N paint/Nerolac) on old wall surface to give an even shade after thoroughly brushing the surfaces free from mortar droppings and other foreign matter and sand papered smooth. (a) Plastic Emulsion Paint of approved brand and manufacture (Asian paint/Berger paint/ ICI paint/ J& N paint/ Nerolac). (including subsequent coat)	1232.50	SQM		
2	Providing two coats of Birla White Wall Care Putty (Water Resistant White Cement based putty for concrete/mortar walls and ceiling both internal and external) after removing all loosely adhering material from the wall surface with the help of emery stone, putty blade or wire brush and moistening the wall with sufficient quantity of clean water as specified and directed by the department.(Total thickness of two coat is maximum 1.5mm) (i)Thickness = 1.5 mm thick	120	Sqm		
3	a) Applying one coat of cement primer of approved brand and manufacture on new wall surface after thoroughly brooming the surfaces free from mortar droppings and other foreign matter and including preparing the surface even and sand papered smooth	120	Sqm		
4	Finishing old / new wall with water proofing weather coat smooth anti-fungal exterior painting of approved make of Berger paint of required shade after cleaning and clearing the surface etc. including scaffolding complete as directed at all levels (two Coats)	515.73	Sqm		

5	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint of approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ j & N paint/ Nerolac) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. (i) Surfaces over 100mm in width or girth. a) General purpose (Asian paint/ Berger paint/ ICI paint/ j & N paint/ Nerolac). Including window shutter	182.16	sqm		
6	Painting one coat (excluding priming coat) on old wood and wood based surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter sand papering and stopping. (i) Surfaces over 100mm in width or girth. a) General purpose (Asian paint/ Berger paint/ ICI paint/ j & N	131.25	SQM		
7	Distmanteling all types of corrugated sheet roofing including ridges, hips, valleys and gutters etc. and stacking the materials as directed by the department for all levels	11.13	sqm		
8	Providing corrugated galvanised Iron sheet roofing of TATA SHAKTEE / SAIL including fitting and fixing necessary galvanised J or L hooks, bolts and nuts 8mm dia x 3 mm thick and 1.6 mm thick limpet washer complete excluding cost of roof truss, purlin etc. (Roof trusses and purlin etc. to be measured and paid separately). (a) 0.45 mm thick	11.13	sqm		
9	Supplying, fitting and fixing in position reinforcement bar conforming to relevant I.S. Code for R.C.C work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, Suppling and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. (No extra measurement for lap, hook, chair, anchor etc. will be entertained in the measurement as they are included in the rate) (Upto 1st floor level) a) From Primary Producer: TATA/SAIL/JINDAL steel/shyam steel/RINN (l) tmt CORROSION RESISTANT STEEL (CRS) reinforcement bar	0.2558	Qtl		

10	Providing form work of ordinary timber planking so as to give a rough finish including centering,shuttering,strutting and propping etc., height of propping and centering below supporting floor to ceiling not exceeding 4.0M and removal of the same for in-situ reinforced concrete and plain concrete work in: 3.1.1.2 Sides of tie beams, grade beam etc. at or below ground level (a) Using 38mm thick plank	2.00	sqm		
11	Column, Pillars, Posts & Strut (a) Using 38mm thick plank	1.11	sqm		
12	Prviding soling in foundation and under floor with stone/best quality picked and laid to level and in panel after preparing the subgrade as directed including all labour and materialsand if necessary dewatering complete. (a) Brick on flat soling.	1.18	sqm		
13	1st class brick nogged wall in cement mortar including racking out joints and curing complete as directed in super structure above plinth up to 1st floor level (protruding M.S rod/Tor steel of column to be embeded in cement mortar and will be measured and paid separately) (A) 112 mm thick brick wall (a) In cement mortar in proportion 1:4(1 cement:4 sand)	7.66	SQM		
14	15 mm thick cement plaster in single coat on single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed A) On rough side a) In cement mortar 1:4	18.8	SQM		

15	Providing and laying plain/reinforced concrete works cement, coarse sand & 20mm down graded stone aggregate including dewatering if necessary, and curing form, etc. but excluding cost of form work and reinforcement for reinforced concrete work (form work and reinforcement will be measured and priced separately)	0.23	cum		
	(i) Using Mixer Machine				
	(A) In substructure up to plinth level				
	Foundation, footing, column with base tie and plinth beam, pile cap, base slab, retaining walls, walls of septic tank, inspection pit and the like and other works not less than 100mm thick up to plinth level.				
	N) Without using admixture, plasticiser				
	b) M20 grade concrete or Prop 1:1.5:3				

(Including all taxes)

Total

Total (in words):

Contractor's Name:- _____

Address :- _____

Registration No :- _____