



ASSAM TEA EMPLOYEES PROVIDENT FUND ORGANIZATION

(Formerly Known as The Assam Tea Plantations Provident Fund & Pension Fund Scheme & D.L.I. scheme)
Sivasagar Zone, D.N. Bezbarua Path, Sivasagar-785640; Ph: 03772-222356, E-mail: atppf.siv@gmail.com.

No. PF/ZO-SIV/2026/TENDER/ 650

Dated Sivasagar 23.10.2026

Tender Notice

Sealed quotation affixing court fee stamp of Rs. 8.25 (non - refundable) are invited by the undersigned from registered appropriate Contractors/Firms in prescribed Form for the following works will be received in the office of the ATEPFO, Sivasagar Zonal Office, Sivasagar, upto 2.00 PM on 02.11.2026 and opened at 2.00 PM on the same day.

1. **Name of work** : Construction/Improvement of Approach Road and Internal Road and Office Front at ATEPFO, Sivasagar Zonal Office Building (Assam Type) at Sivasagar.
2. **Estimated value** : Rs.2,64,327.00 (Rupees Two Lacs Sixty Four Thousand Three Hundred & Twenty Seven Only).
3. **Rate to be quoted** : On supplied prescribed Form's bill of quantities & Total Quoted value also added (including all taxes).
4. **Earnest Money** : 2% (2 % for general & 1% for ST/SC/OBC/MOBC) on total quoted value in favour of Secy. Cum .P.F.Commissioner, ATEPFO, in form of Demand Draft/Fixed Deposit. Tender shall not claim any interest on Earnest Money deposit.
5. **Time of completion** : 10(Ten)days from the date of issue of formal work order.
6. The up to date IT,GST, Registration, Trade Licence Certificate will have to be enclosed with quotations. The office reserves the right to accept/reject any or all quotations without assigning any reason whatsoever.

Asstt.P.F.Commissioner,
ATEPF Organization,
Sivasagar Zonal Office.

TENDER FORM

NAME OF WORK :- Construction/Improvement of Approach Road and Internal Road and Office Front at ATEPFO Sivsagar z/o Building (Assam Type) at Sivsagar.

SL. NO.	DESCRIPTIONS	UNIT	QTY	RATE	AMOUNT
1	Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. 2.28.1 All kinds of soil	Sqm	394.175		
2	Construction of granular sub-base by providing close graded Material conforming to specifications complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	CUM	39.42		
3	With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	CUM	39.42		
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density .	CUM	29.56		
Total					

Add GST 18% =

Total =

in Words:-

contractors Name:-

Address:-

Registration No :-